

Psion Web Site www.psion.com

Psion Faxback Service 0891 515 432

Setting up your Series 5 with Motorola Ir Phones

Introduction

This document is designed as a step by step guide to help you connect your Series 5 to your Motorola phone for email or web browsing. This document is not designed for anyone but Series 5 users.

Furthermore this document assumes you have installed Message Suite v1.52. At the time of writing the latest version is v1.52 and we strongly recommend that this version be installed.

You can obtain the latest version of Message Suite from our web site http://www.psion.com or install it from the latest PsiWin 2.x CD.

Hardware and Services covered in this document

This document covers the following hardware and services:

Phones

Motorola Timeport L7089

Psion devices

Psion Series 5

Mobile phone services

Data calls for email and web browsing

NOTE: the Series 5 does not contain any SMS software (see Section 5 of this document for more information). Furthermore the Motorola Timeport L7089 does not support fax.

1. Motorola mobile phone setup

- 1. Check your SIM card is enabled for data if you are unsure contact your network provider, who will be able to enable your SIM, if necessary.
- 2. Position both units so that Infrared ports line up at a distance of between 5 to 15cm
- 3. Activate your mobile phones infrared port (please refer to your mobile phones manual for details on how to activate this port.)
- 4. For best result your mobile needs to be displaying good signal strength; i.e. 3 to 5 bars on the mobile phones display window. Note this is network dependent on your cellular provider in your coverage area. Failure to have a good signal strength may lead to intermittent dropped calls.

Please Note

A wireless connection is liable to open air effects, which means that any call over GSM will not be as reliable or as fast as a land line to cable modem setup.

2. Series 5 control panel setup

1. Now press CTRL+S (or tap on the Control Panel button on the right hand toolbar) to open your Series 5 control panel.



- 2. Tap on the 'Modems' icon Modems
- 3. Tap on the 'New' button and enter the data modem configuration so that it is the same as the listed parameters below. Press CTRL+D (or tap on the 'Done' button) when you have finished creating the new modem configuration




- 4. Setup your dialling location details by tapping on the 'Dialling' icon Dialling and selecting 'Mobile' option in the Location Details tab. Tap on 'OK' to confirm your choice.
- 5. Follow the messaging suite instructions for setup of your Internet provider and Email account provider details.

Please Note

Avoid future login problems by closing down your connection to the email/web post office properly i.e. select the option 'close remote mailbox' or 'disconnect from Internet'.

Modem setup parameters from Series 5 control panel



Modem Name Motorola Timeport L7089

Modem Speed 115200
Connect Via Infrared
Fax Class Auto
Loudspeaker in user Never
Volume Quiet
Pause time for "," 4

Init. (reset) string AT&F&K5


Data init. String Empty
Fax init. String Empty

Flow Control Software (XON/XOFF)

Terminal detect (DSR/DTR) No tick Carrier detect (DCD) No tick

3. Testing your Internet connection

NOTE: It is best to test your internet connection with just the web browser as it only requires you to ensure one username and password is correct.



- 1. Start up web by tapping on the Extras icon **Extras** and then tapping on the web icon
- 2. To dial out select mobile for location rather than office or home.



- 3. Ensure you have set the modem setting to "Motorola Timeport L7089"
- 4. Typical Network login time is 20-30 seconds
- 5. Typical download time for the Psion mobile phone connectivity home web page (http://www.mobile.psion.com/) is about 2 minutes, this being dependent on having good cellular coverage and high signal level.

Please Note

• If you receive a dialog that tells you 'Access Denied' this is most likely because you have not turned the Remote Link off, or that the Comms application is running. To remedy the solution, check that the Remote Link is off by pressing CTRL+L when on the system screen, and check that the Comms application is not open by holding down the CTRL button and tapping on the system button. This will display the 'Open files / programs' dialog which will allow you to close down the Comms application if necessary.

4. Troubleshooting using the Comms app

The following method can be used to check that the Series 5 can establish a link with the Motorola Timeport L7089 being used.

• Check the Remote link is set to 'Off' at the Psion end of the link. Go to the System screen and use CTRL+L (or tap 'Remote Link' in the 'Tools' menu) and check that it is set to 'Off'. Press Enter or tap OK to confirm this setting.



• Check that the Infrared port Is activated on the mobile phone



- From the Extras bar Extras open the Comms application Comms
- On the tool bar tap on the 'setup' button, and choose Infrared under settings. Confirm by tapping on the 'OK' button.
- Press menu and tap on 'tools', then tap on translate codes and check that local echo is not ticked. Confirm by tapping on the 'OK' button
- You should see 'on-line' in the lower left of the Series 5 screen.
- Type 'ATI' and press return. You should receive a prompt of either "960" when the interface between Series 5 and mobile phone is working correctly.
- Press CTRL-E once you have finished testing the link between the mobile phone and the Series 5.

5. Notes regarding other services over Infrared

- 1. You cannot send or receive SMS messages on the Series 5 via Message Suite
- 2. You cannot send contact information over Infrared to the Series 5 via Message Suite
- 3. There is a 3rd party software that allows you to have Phone Book management capabilities over infrared found at http://www.sgsoftware.co.uk/
- 4. It is possible for the Motorola handset to get into a situation where you can send SMS messages using your Psion device, but not bring messages, that the handset has already received, onto it. If this occurs it can be easily resolved by turning the handset off and then on again.